DAM CONSTRUCTION AND No. I. IRWIN CANAL DIVISION, KRISHNARAJASAGARA.

Dated 1st August 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Dam Construction and No. I, Irwin Canal Division, Krishnarajasagara, up to 4 P.M. of 29th August 1932, for the work of constructing two Officials' Quarters of No. 3 type design at Yedatore New Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1933.

2. The plan, detailed estimate and conditions may be seen at the Executive Engineer's Office at Krishnarajasagara between the hours of 11-30 A.M. and 5-30 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred only (Rs. 200) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing two Officials' Quarters of No. 3 type design at Yedatore New Town" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for constructing two Officials' Quarters of No. 3 type design at Yedatore New Town.

Sl. No.	Items of work	Unit	Quantity
	Estimate of quantities for constructing 1 Quarters.		
1	Clearing site levelling ground and forming ...	Lump.	sum
2	Earth work excavating foundation and filling in basement with consolidation.	C. yd.	51
3	Stone jelly concrete in sand mortar ...	C. ft.	558
4	Size stone in mud ...	,,	910
5	Burnt brick in mud ...	,,	1,700
6	Burnt brick in mortar ...	,,	550
7	Burnt stone slabs 2 line dressed ...	S. ft.	140
8	Teak wood work wrought and put up with wood oiling ...	C. ft.	65·6
9	Roofing with 1st class Mangalore tiles on teak reepers with nailing, etc.	Sqr.	13·79
10	Ridge tiles set in mortar and cement pointed ...	R. ft.	97
11	Pucca terrace roof 9" thick complete ...	Sqr.	1·01
12	Ordinary parapet wall with 6" cornice ...	R. ft.	28
13	Teakwood battened doors with hinges, bolts, etc. ...	S. ft.	194
14	Teakwood windows with iron bars ½ glazed and ½ battened doors complete.	,,	48
15	Teakwood ventilators with iron bars, battened shutters, hinges, etc.	,,	48

Sl. No.	Items of work	Unit	Quantity
16	Teakwood wall shelves with 3 rows of planking, etc., complete ...	S. ft.	24
17	Mortar bands over roof ...	R. ft.	82
18	Flooring with Vajragare ...	Sqr.	6·13
19	Flooring with Kadappa slabs on 3" concrete and cement pointing.	,,	103
20	Providing and fixing pestle and mortar ...	Pair.	2
21	Cornice 9" thick ...	R. ft.	31
22	Teakwood eave board (plane) 9" x 1" with chocolate painting.	,,	192½
23	Teakwood pendants ...	Nos.	5
24	Constructing a combined smoke chimney with expanded metal as per design.	,,	1
25	Coping with brick in mortar complete ...	R. ft.	53
26	(a) Providing and fixing teakwood planks with plugs ...	S. ft.	15
	(b) Providing and fixing stone benches ..	,,	21
27	(a) Constructing a sink in bath room ..	No.	1
	(b) Do in kitchen ..	,,	1
28	Constructing jelly concrete drain with cement plastering ...	R. ft.	60
29	Constructing seats in latrine ...	Lump	sum
30	Supplying and fixing galvanized zinc spouts ..	Nos.	2
31	Chunam plastering ...	Sqr.	44·49
32	White washing 2 coats ..	,,	44·49
33	Chunam pointing and cement rendering ...	,,	2·52
34	Chocolate painting 2 coats ..	,,	6·28
35	Water tap connection, including construction of cistern, lead off drain, etc.,	Lump	sum
36	Sundries and unforeseen charges ...	Lump	sum

N. SARABHOJA,
Executive Engineer.

BANGALORE DISTRICT.

Notification No. Ex. 5-35—32-33, *dated* 1*st August* 1932.

In exercise of the powers conferred by clause 7 of general conditions in Part III of Government Notifications No. Fl. 5515—Ex. 78-29-2, dated 17th February 1930, Fl. 6587—Ex. 70-30-2, dated 20th February 1931 and Fl. 6633—Ex. 79-31-2, dated 20th February 1932, notice is hereby given for the general information of all the Excise Opium and Ganja Licensees of the Bangalore District, that the undermentioned quantities of Exciseable articles are prescribed as the minimum and maximum stocks to be maintained in the Excise and Opium shops of the district during the official year 1932-33.—

Serial No.	Shops	Arrack		Special liquors		Ganja		Opium		Country Beer		Foreign Liquors		Toddy
		Minimum	Maximum	Minimum	Maximum	Minimum	Maximum	Minimum	Maximum	Minimum	Maximum	Minimum	Maximum	
		Gls.	Gls.	Gls	Gls.	S.T.	S.T.	S.T.	S. T.	Gls.	Gls.	Gls.	Gls.	
1	Bangalore City area.	30	120	10	50	0 40	4 0	0 30	2 0	5	30	30	200	Stock equal to one day's consumption.
2	Taluk Head-quarters.	2	20	...	..	0 30	2 0	0 5	1 0	..	...	...	..	
3	All other shops...	1	12	...	..	0 20	2 0	0 5	1 0	...	...	...	..	

K. V ANANTARAMAN,
Deputy Commissioner.